

1 120530

2-11-91

149

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,817-0000

SE SW SE, SEC. 17, T 24 S, R 14 W/E

330 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name Denker "B" Well # 1

Operator: Vess Oil Corporation PV Properties,  
Name & Address 8100 E. 22nd N, Bldg. 300  
Wichita, KS 67226

County Stafford 140.30

Well Total Depth 4317 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 11 Month: 2 Year: 19 91

Plugging proposal received from L.D. Davis

(company name) L.D. Drilling (phone) 316-793-3051

were: 5 1/2" at 4317' w/175 sx cement, Open hole

1st plug sand back to 4260' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

2-18-91  
FEB 18 1991

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 11 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4260' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1220' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-5-91

INV. NO. 310 12

Signed \_\_\_\_\_ (TECHNICIAN)