

2 030714

10-3

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 015-22,056 ~~00-00~~

C S/2 NE SW, SEC. 28, T 27 S, R 6 W/E

1650 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name Simmons "A" Well # 2

Operator: Range Oil Co., Inc.

County Butler 100.04

Name & Address 1120 KSB Bldg., 125 N. Market

Well Total Depth 3078 feet

Wichita, KS 67202

xxxxxxx Pipe: Size 4-1/2" feet 3077'/100 SX

Surface Casing: Size 8-5/8" feet 208'/150 SX

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P. O. Box 108 Geneseo, KS 67444

Company to plug at: Hour: Day: 27 Month: 9 Year: 19 88

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6483

were: Sand or gravel to 2960' - dump 4 sx cement - shoot & pull casing - bail  
hole 300' - set rock bridge 275' - dump redimix to surface.

Perf 3016' to 3020'

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 13:45 Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Sanded hole to 2960' - dumped 4 sx cement w/bailer - shot  
and pulled 2450' of 4-1/2" casing - could not bail hole to 300' - United

Cementing #2766 pumped 3 sx hulls, 10 sx gel, 100 sx 60/40 posmix 12% EG 10 down  
8-5/8" surface casing - pump pressure 800# - SIP 300#.

STATE CORPORATION COMMISSION

NOV 4 1988

11-01-88  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: top plug

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 11-3-88

Signed Don Thompson (TECHNICIAN)

INV. NO. 22889

10-3