

1-29

2-030986

177
R4

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-015-20,253-0500 E-15,267

C Lot #1, SECTION 7 TOWNSHIP 27 RANGE 8E

OPERATOR LICENSE # 6407 4950 FEET FROM S SECTION LINE
4000 FEET FROM E SECTION LINE

OPERATOR Flowers Production Co., Inc
NAME & P. O. Box 249
ADDRESS El Dorado, KS 67042

LEASE NAME: Smith #2
COUNTY: Butler 101.27
WELL TOTAL DEPTH: 3116' P.B. 2847'
PIPE: 5-1/2" @ 2847'/75 sx
SURFACE CASING: 8-5/8" @ 205' C.T.S.

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Dale Wilson
ADDRESS: RR #3, El Dorado, KS 67042 LICENSE: 6012

COMPANY TO PLUG AT: HOUR: _____ DAY: 8 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Dallas Flowers
COMPANY NAME: Flowers Production Co., Inc. PHONE: 316-321-0550

WERE: Spot cement plug on bottom - rip and pull csg - set
bridge 300' - cmt to surface.
Perf 2662' to 2668'

PLUGGING PROPOSAL RECEIVED BY: District #2 office

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: _____ DAY: 29 MONTH: 1 YEAR: 1991

ACTUAL PLUGGING REPORT:
Tried to fish tub and get down 5-1/2" csg - reached
97' - could go no further - used washover pipe and got
to 142' - almost lost pipe - pulled washover pipe and
ran 3/4" pipe to 142' - United #1204 pumped 114 sx
60/40 posmix 2% gel to surf - pulled 3/4" - filled
hole. Checked water well files, estimate that deepest screened
interval in area @ depth shallower than 142' - MLK

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 3-1-91

INV. NO. 30949

FEB 14 1991

CONSERVATION DIVISION
Wichita, Kansas

Don Thompson
Don Thompson (AGENT)

FORM CP-2/3
REV. 3/90