

325(14g)

2 030448

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-015-22,250-00-00  
NW, SEC. 7, T 27 S, R 8 #1E

4640 feet from S section line  
4136  
4536 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6228  
Operator: Saco Oil Company  
Name & Address: Box 231  
El Dorado, Ks. 67042

Lease Name Bennon Well # 1  
County Butler 91.33  
Well Total Depth 2810' feet  
Conductor Pipe: Size 5 7/8" feet 2810' / 100' 24  
Surface Casing: Size 8 5/8" feet 205' / 150' 24

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B+S Well Services Inc. License Number 6015

Address Box 837, Winfield, Ks 67156

Company to plug at: Hour: 09:00 Day: 24 Month: 7 Year: 19 86

Plugging proposal received from Dale Smith

(company name) B+S Well Services Inc. (phone) 316-221-2030

were: Perf. 2750' to 2755' Fill hole / chat to 2700' dump. Top cement  
shot + pull 5 1/2" csg. rock bridge 275' to 250' dump  
redi-mix to top of sur. casing.

Plugging Proposal Received by Ron Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 13:45 Day: 28 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Filled hole / chat to 2700', dumped. Top cement / bridge  
shot + pulled. 1242' of 5 1/2" csg. bailed hole to 275'. rock  
bridge 275' to 250'. Lewis + West Redi-mix # 03922  
dumped 3 yds redi-mix to top of surface casing.

7-7-86

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging.

Signed Ron Thompson  
(TECHNICIAN)

DATE AUG 8 1986  
INV. NO. 14684