

2 030449

318(133)

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-22,298-00-00

NW, SEC. 7, T. 27 S, R. 8 W/E
2960' feet from S section line
4950' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6228

Lease Name Bannon Well # 2

Operator Name & Address: Saco Oil Company
Box 231

County Butler 52.26

El Dorado, Ks. 67042

Well Total Depth 1608' feet

Conductor Pipe: Size 5 1/2" feet 1608' / 755x

Surface Casing: Size 8 5/8" feet 215' / 15024

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B+S Well Services Inc. License Number 6013

Address Box 837 Winfield, Ks. 67156

Company to plug at: Hour: 11:00 Day: 29 Month: 7 Year: 19 86

Plugging proposal received from Wale Smith

(company name) B+S Well Services Inc (phone) 316-221-2030

were: Perf. 1549' to 1557' Fill hole/chart. 1500' dump. 75% cement. shoot + pull 5 1/2" csg. rock bridge 290' to 265', fill with sedi-mix to top of sur. csg.

Plugging Proposal Received by Alan Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 16:15 Day: 30 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Fill hole/chart. to 1500', dumped 75% cement with trailer, shot + pulled. 1123' of 5 1/2" csg., rock bridge from 290' to 265', Lewis and Clark Sedi-mix. # 03924 dumped 5 yds (sand + cement) to top of surface casing.

08-07-86
AUG 7 1986

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG - 8 1986
INV. NO. 14677

Signed Alan Thompson (TECHNICIAN)