

2 090054

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,418 -0000

W/2 SENE, SEC. 24, T 27 S, R 6 WXX

3300 feet from ~~W/2~~ section line

660 feet from ~~W/2~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6236

Lease Name Schrag Well # 1

Operator: MTM Petroleum

County Kingman

Name & Address Box 82

Well Total Depth 4220 137.15 feet

Spivey, Ks. 67142

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 348'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation, Medicine Lodge, KS License Number 5105

Address _____

Company to plug at: Hour: 9:30 a.m. Day: 2 Month: 10 Year: 19 84

Plugging proposal received from _____

(company name) _____ (phone) _____

were: Bottom plug-sand back to 3715' with 5 sacks

Top plug-60-40 3-2% pumped 1 hull and 135 sacks, 2 hulls 6 Gel; 1 hull & 135 sacks from 348' to surface 100 ISIP

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 a.m. Day: 2 Month: 10 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 3715' and 5 sacks

of cement were spotted on top of the sand through the bailer. The pipe was short off

and 3200' of 5 1/2" was recovered. The top was plugged by pumping 2 sacks of hulls,

6 sacks of Gel, 1 sack of hulls and 135 sacks of 60-40 cement to surface.

Instant shut-in pressure was 100

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1984
10-09-84

Remarks: Allied Ticket #38466

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED (did not) observe this plugging.

Signed David White (TECHNICIAN)

DATE 10-15-84

INV. NO. 4315

RO
FORM CP-2/3
Rev. 01-84