

2090027

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-21,473-0000

SE $\frac{1}{4}$ /NE $\frac{1}{4}$ , SEC. 24, T 27 S, R 6 ~~W~~ ~~XX~~

2310 feet from ~~N~~ section line

660 feet from ~~XX~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6236

Lease Name Schrag Well # 2

Operator: MTM Petroleum

County Kingman

Name: MTM Petroleum  
Address Box 82, Spivey, Ks. 67124

Well Total Depth 4165 135.36 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 340' 50'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling License Number 5829

Address 453 S. Webb Rd., Box 18611, Wichita, Ks. 67202

Company to plug at: Hour: 2:00 p.m. Day: 28 Month: 7 Year: 19 84

Plugging proposal received from \_\_\_\_\_

(company name) K.C.C., Salina, Ks. (phone) \_\_\_\_\_

were: 50 sacks @ 900' 1 50 Sacks @ 400'; 50 sacks @ 60'; 10 in rat; 10 in mouse

RECEIVED

STATE CORPORATION COMMISSION

AUG 02 1984

Plugging Proposal Received by Toman

CONSERVATION DIVISION  
Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 2:15 p.m. Day: 28 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with heavy drilling mud; run drill pipe to 900'

spotted 50 sacks of cement through drill pipe; pulled drill pipe to 400', spotted

50 sacks of cement through drill pipe; wood and rubber plug set at 60' with 25 sacks

of cement circulated to surface; run one joint of drill pipe in rat circulated

10 sacks cement to surface; 10 sacks of cement in mouse hole circulated

GOOD CEMENT

Remarks: Alleid Ticket #37145 50-50 pos; 2% gel

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) / (did not) observe this plugging.

DATE 8-4-84

WK

Signed Dan W. [Signature] (TECHNICIAN)

RO

INV. NO. 2854