

2090037

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-21,480-0000

NWSENE, SEC. 24, T 27 S, R 6 @/E

1650 feet from N/XX section line

990 feet from XXE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6236

Lease Name Schrag Well # 3

Operator: M.T.M. Petroleum

County Kingman

Name & Address: Box 82, Spivey, Ks. 67142 ±

Well Total Depth 3780 122.85 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 268'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address 1105 Walnut, P.O. Box 1389, Great Bend, Ks. 67530

Company to plug at: Hour: 3:00p.m. Day: 15 Month: 8 Year: 19 84

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 35 sacks at 800'; 35 sacks at 300'; 20 sacks at 40' 10 in rat 60-40 pos 3%cc

K.C.C. Plugging Proposal Received by Glen Ward (TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 4:10p.m. Day: 15 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with heavy drilling mud; run drill pipe to 800'

spotted 35 sacks cement through drill pipe; pulled drill pipe to 300' spotted

35 sacks cement through drill pipe; pushed a wood and rubber plug to 40'; spotted

20 sacks of cement through drill pipe; run one joint of drill pipe into rat hole

circulated 10 sacks of cement to surface

Remarks: Sun of Medicine Ticket #19164 (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

08-20-84 AUG 20 1984

INVOICED observe this plugging.

DATE 8-21-84

Signed David White (TECHNICIAN)

INV. NO. 3320 8-15

CONSERVATION DIVISION Wichita, Kansas FORM CP-2/3 Rev. 01-84