

4-30

2-070705

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-095-21,723-0000

SW SW, SECTION 32 TOWNSHIP 27 RANGE 6W

OPERATOR LICENSE # 5399 660 FEET FROM S SECTION LINE  
OPERATOR AMERICAN ENERGIES CORPORATION 660 FEET FROM @ SECTION LINE  
NAME & 155 NORTH MARKET, SUITE #710  
ADDRESS WICHITA, KS 67202

LEASE NAME: VORAN #1  
COUNTY: KINGMAN  
WELL TOTAL DEPTH: 3981' 129.38  
PIPE:  
SURFACE CASING: 8 5/8" @ 221'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A X

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: WHITE & ELLIS DRILLING, INC

ADDRESS: P.O. BOX 48848, WICHITA, KS 67201 LICENSE: 5420

COMPANY TO PLUG AT: HOUR: 9:00AM DAY: 30 MONTH: 4 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: ROBERT KASPER

COMPANY NAME: WHITE & ELLIS DRILLING, INC PHONE: (316) 263-1102

WERE: 35 SACKS AT 950'  
35 SACKS AT 450'  
85 SACKS AT 250'  
15 SACKS IN RATHOLE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { X }

COMPLETED: HOUR: 2:30 DAY: 30 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: RAN DRILL PIPE TO 950' AND PUMPED 35 SACKS. PULLED TO 450', PUMPED 35 SACKS. PULLED TO 250', PUMPED 85 SACKS TO SURFACE. RAN JOINT OF DRILL PIPE IN THE RATHOLE AND PUMPED 15 SACKS TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

I DID NOT OBSERVE THIS PLUGGING.  
*Jack Luthi*  
JACK LUTHI

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 25 1997  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
JUN 25 1997  
DATE  
INV. NO. 48401

DW