

12-29

1040211

API NUMBER 15-185-21,327-0006

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-4-89  
JAN 4 1989

NW SE NE, SEC. 7, T 24 S, R 15 W&X

3630 feet from S section line

990 feet from E section line

Operator License # 5135

Lease Name Whitzel Well # 1

Operator: John O. Farmer, Inc.

County Stafford 134.23

Name & Address Box 352

Well Total Depth 4130 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 12 Year: 19 88

Plugging proposal received from Jerry Allen

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4129' PBD 4084' Perfs at 4050-4060'

1st plug pump 25 sx common cement and 1 sx hulls to 3900',

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 100 lbs. hulls, 25 sx common cement,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(old) (X&X&X) observe this plugging.

DATE 1-9-89

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INV. NO. 23548