

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-095-21,102-0000

LEASE NAME Reno #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NE SE

SEC. 29 TWP. 27S RGE. 5W (E) or (W)

COUNTY Kingman

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/11/84

Plugging Completed 7/17/84

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR F & M Oil Co., Inc.

ADDRESS 422 Union Center, Wichita, Ks. 67202

PHONE # 316 262-2636 OPERATORS LICENSE NO. # 5313

Character of Well \_\_\_\_\_  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4325'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	325'	none
				4 1/2"	3875'	2990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3720' & 4 sacks cement. Shot pipe at 3364', 3207', & 2990'. Pulled 74 joints of pipe. Plugged well with 3 hulls, 10 gel, & 185 sacks 50/50 poz.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address C - Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1984



My Commission expires:

Irene Hoover  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 26 1984  
 7-26-84  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-095-21102-0000

CONTRACTOR'S WELL LOG

OPERATOR:	F & M OIL CO., INC.
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	Reno #1
LOCATION:	C NE SE Section 29-27S-5W Kingman County, Kansas
COMMENCED:	July 15, 1981
COMPLETED:	July 24, 1981

0	325	Redbed	Set 8-5/8" @ 325' w/225
325	1313	Shale	sxs common 2% gel, 3% CC
1313	1594	Shale & lime	
1594	3115	Shale	
3115	3335	Shale & lime	
3335	3492	Shale	
3492	3647	Shale & lime	
3647	3795	Lime & shale	
3795	4325	Lime	
4325		TD	

We certify that the above foregoing is a true and correct copy of the log on the Reno #1, C NE SE Section 29-27S-5W, Kingman County, Kansas.

Union Drilling Co., Inc.


*R. D. Messinger*  
 R. D. Messinger

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 29th day of July, 1981.

My appointment expires:  
12-24-84

*Shirley A. Gallegos*  
 Shirley A. Gallegos  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 06 1984  
 CONSERVATION DIVISION  
 Wichita, Kansas