

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD

OR

**Strike out upper line
when reporting plug-
ging off formations.**

FORMATION PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harvey County. Sec. 11 Twp. 23 Rge. 2 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW, I/4, SW, I/4, NE, I/4

Lease Owner Harbar Drilling Co., Etal

Lease Name Berger Well No. 1

Office Address 1019 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 6/22 1945

Application for plugging filed 11/27/48 Verbal 19

Application for plugging approved 11/27/48 Verbal 19

Plugging commenced 11/29/48 19

Plugging completed 12/2/48 19

Reason for abandonment of well or producing formation Making too much water to produce commercialy

If a producing well is abandoned, date of last production 11/7/48 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. M. Muel Durkee
Producing formation Chat Depth to top 2932 Bottom 2971 Total Depth of Well 2971 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to feet for each plug set.

Filled hole with crushed rock from T.D. (2971) to 2943' and dumped 5 sacks cement filling 5 1/2" casing to 2908'

Filled hole with heavy mud to 250' and set wooden plug. Cemented on top plug w/ 25 sacks filling hole to 210'. Dumped heavy mud on top cement to 5 feet top and dumped 5 sacks cement filling top surface casing and bottom cellar.

Note. Surface sasing was cemented top to bottom at time it was set.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Co.,
Address 1019 Central Bldg. Wichita Kansas.

STATE OF Kansas, COUNTY OF Barber, SS.
Paul Hunter (employee of owner) or ~~owner or operator~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God.

(Signature)

SUBSCRIBED AND SWORN to before me this 7th day of December, 1948

My commission expires.

PLUGGING 222625
FILE SEC 14-23R
BOOK PAGE 70 LINE 33

2-48--15M

.....
Notary Public.

15-079-00780-0001

HARBAR DRILLING CO., ET AL
 BERGER #1
 SWc NE $\frac{1}{4}$ 14-23-2W, HARVEY CO., KANSAS

Rigging up 5-8-45

Tearing down 5-26-45

Ran 11 Joints 10 3/4" 10 thread surface casing; cemented with 150 sacks cement and 100 lbs of calcium chloride

Ran 94 Jts of 5 $\frac{1}{2}$ " casing. Set @ 2943' and cemented with 75 sx cement.

FORMATION	FROM	TO
Shale surface	0	30
Sand and gravel	30	100
Shale blue	100	159
Shale and shells	159	340
Anhydrite	340	370
Lime	370	485
Lime and shale	485	550
Lime and shale	550	970
Lime	970	1000
Shale	1000	1118
Shale and lime	1118	1240
Shale and shells	1240	1375
Shale	1375	1475
Broken lime	1475	1580
Lime and shale	1580	1765
Lime	1765	1785
Lime and shale	1785	1840
Lime shells & shale	1840	1925
Lime shale	1925	1940
Lime	1940	2015
Broken Lime	2015	2095
Lime	2095	2155
Lime broken	2155	2348
Lime, cherty, rough	2348	2368
Lime broken	2368	2375
Lime	2375	2385
Broken lime	2385	2500
Lime	2500	2630
Shale and lime	2630	2665
Lime	2665	2830
Shale	2830	2900
Shale and lime	2900	2935
Chat	2935	2960
Slate	2960	2965
Chat	2965	2971

Total Depth

RECEIVED

Conservation Div.

DEC 10 1948

STATE CORPORATION
 COMMISSION
 KANSAS

I, Don S. Packer, hereby certify that the above log is true and correct,
 to the best of my knowledge and belief.

Subscribed and sworn to before me this 9th day of December, 1948.

Notary Public

My commission expires: March 22, 1952

