

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

15-079
20109-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Harvey County, Sec. 14 Twp. 23 Rge. 2 W (E) (W) X X

Location as "NE/CNW/SW" or footage from lines C/East 30-E/2-NW
Lease Owner Charles Carlock
Lease Name Berger Well No. 1
Office Address 1515 Hillcrest Newton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed January 22, 19 73
Application for plugging approved 19
Plugging commenced February 8, 19 73
Plugging completed February 13, 19 73
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 3449 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	195	None
				5 1/2	3448	2160.52'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured T. D. Dumped sand to 2900 ft. and 5 sacks cement. Shot casing at 2550 (14" - 2500psi). Shot casing at 2470 (21" - 2500psi). Shot casing at 2360, 2250 and 2155 ft. Pulled 63 joints of 5 1/2" casing. Plugged well with mud to 220 ft. and dumped a rock bridge to 210 ft. Dumped 25 sacks cement and mudded hole to 40 ft. Built a 10 ft. rock bridge to 30 ft. and capped well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1973
2-15-73
CONSERVATION DIVISION
Wichita, Kansas

(if additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold
James W. Rockhold
Box 698 Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 73

My commission expires September 30, 1975

Cathy Miller
Cathy Miller Notary Public.

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 653-2381
HOISINGTON, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 - UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

15-079-20109-0000

May 26, 1969

Company;	Charles Carlock
Farm;	Berger #1
Location;	C E/2 E/2 NW
Section;	14-23-2W
County;	Harvey
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	May 16, 1969
Compl;	May 25, 1969
Total Depth;	3449
Casing;	8 5/8" @ 195 w/130 sacks 5 1/2" @ 3447.97 w/200 sx.
Elevation;	1436 K.B.

Figures Indicate Bottom Of Formations:

150	Clay
195	Shale
290	Shale
645	Lime
905	Lime
1230	Lime & Shale
1555	Lime & Shale
1775	Lime & Shale
1995	Lime & Shale
2185	Lime
2320	Lime
2475	Lime
2497	Lime
2505	Lime
2595	Lime
2641	Lime
2750	Lime
2890	Lime & Shale
2966	Lime & Chert
3095	Lime
3160	Lime
3235	Lime & Chert
3290	Lime & Chert
3345	Lime
3405	Lime
3449	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1973
CONSERVATION DIVISION
Wichita, Kansas

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman

JAN 22 1973
AK