

API NUMBER 15-079-20,321-0000

LEASE NAME Newfield

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 14 TWP. 23 RGE. 2 (E) or (W)

COUNTY Harvey

Date Well Completed 1977

Plugging Commenced 3-3-92

Plugging Completed 3-13-92

LEASE OPERATOR Bear Petroleum Inc

ADDRESS Box 438 Haysville Ks 67060

PHONE# (316) 468-5161 OPERATORS LICENSE NO. 4419

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-1-92 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Miss. Depth to Top 2960' Bottom 2961' T.D. 3050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surt Pipe	Surt	201	2 7/8"	201'	0'
	Reel Casing	Surt.	3050	5 1/2"	3050	1515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped sand from 2970' to 2850' dumped 5 sack cement on bottom, pulled 1515' casing, ran 2" to 500' spud 35 sack cement, pulled plug to 250' pipe cement to set, filled up to surt later

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gresel Oil Field Service Inc License No. 3004

Address Box 607 Burton Ks 67020

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum Inc

STATE OF _____ COUNTY OF _____

(Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Shuman


(Address) Box 438 Haysville Ks 67060



AND SWORN TO before me this 9th day of April, 19 92

Debra K. Hill-Johnson
 Notary Public

My Commission Expires: April 15, 1995



14-23-2W

WELL LOG

15-079-26321-000

SW NW NW

API: 15-079-20,321

Operator Chas. Sanders Oil Co.
 Comm _____ Comp _____
 Shot _____ Qts. From _____ ft. To _____ ft.
 Acidized _____ Gal. _____
 Prod. Formation _____
 Initial Prod. _____
 Elevation _____

Lease Neufeld Well No. 2
 Loc SW NW NW Sec 14 Twp 23 Rge 2
 County Harvey State Kansas
 Contractor Triangle Drilling

Casing Record			
Size	Ft.	Pulled	Remarks
8 5/8	190	85	sks cement
5 1/2	3067	100	sks cement

K. G. S. LIBRARY

FIGURES INDICATE BOTTOM OF FORMATION

0	190	Surface
190	405	Shale
405	720	Shale & Lime stk.
720	975	Shale & Lime
975	1628	Shale
1628	1840	Shale & Lime
1840	2286	Shale
2286	2466	Lime & Shale
2466	2565	K.S.
2565	2706	Lime & Shale
2706	2800	Lime
2800	2869	Lime, Almont
2869	2906	Lime
2906	3135	Miss
3135	3180	Lime & Shale
3180	3252	Hunton
3252	3351	Lime RTD

K. G. S. LIBRARY

RECEIVED
STATE OIL & MINERAL COMMISSION

OCT 02 1991

OBSERVATION DIVISION
Wichita, Kansas

CHAS. W. SANDERS OIL CO., INC. 6-78
 910 SUTTON PLACE 12 NEUFELD
 WICHITA, KS.
 CONTR TRIANGLE DRG. CO. CTY HARVEY

14-23-2W
SW NW NW

GEOL _____ FIELD HALSTEAD

E 1435 KB CM 10/12/77 CARD ISSUED 5/25/78 IF P. 25 BOPD + WTR
 MISS 2960-66

API 15-079-20,321

LOG	TOPS	DEPTH	DATUM
LANS	2318	-883	
BKC	2712	-1277	
MARM	2728	-1293	
MISS	2928	-1493	
KIND	3174	-1739	
HUN	3187	-1752	
MAQ	3241	-1806	
VIOLA	3287	-1852	

8-5/8" 201/60sx, 5 1/2" 3050/100sx
 MICT - PF 2960-66, AC 300, REC LD, POP

