

LEASE NAME Neufeld

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4950 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 14 TWP. 23 RGE. 2 (E) or (W)

COUNTY Harvey

Date Well Completed 1977

Plugging Commenced 3-3-92

Plugging Completed 3-13-92

LEASE OPERATOR Bear Petroleum Inc.

ADDRESS Box 438 Haysville Ks 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well good

(OIL) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-1-92 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? No

Producing Formation Miss Depth to Top 2935 Bottom 2961 T.D. 3494

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surt Pipe	Surt	206	8 5/8	206	0
	Prod Casing	Surt	3895	5 1/2"	3895	605'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Dumped sand from 2965' to 2875' dump bailed cement 5.5" x 30' shot casing at 605' pulled pipe R.H. 2" thg to 500' spotted 3.5" x 30' plug, pulled tubing top to 250' circ. cement to surf, let set two days filled up to surf with redmix

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service Inc. License No. 3004

Address Box 607 Billton Ks 67020

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum Inc.

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Don Thompson

(Address) Box 438 Haysville Ks 67060

AND SWORN TO before me this 9th day of April, 19 92

Debra K. Hill-Johnson  
 Notary Public

My Commission Expires: April 15, 1995



15-079-20293 0000

WELL LOG

Newfield

Operator Charles Sanders Oil Co.  
 Comm \_\_\_\_\_ Comp \_\_\_\_\_  
 Shot \_\_\_\_\_ Qts. From \_\_\_\_\_ ft. To \_\_\_\_\_ ft.  
 Acidized \_\_\_\_\_ Gal. \_\_\_\_\_  
 Prod. Formation \_\_\_\_\_  
 Initial Prod. \_\_\_\_\_  
 Elevation \_\_\_\_\_

Lease Newfield Well No. 1  
 Loc en2 nw nw Sec 14 Twp 23 Rge 2w  
 County Harvey State Kansas  
 Contractor Triangle Drilling Co.

Casing Record

Size	Ft.	Pulled	Remarks
8 5/8	206	150	sks cement
5 1/2	3395		

RECEIVED

NEW COMMISSION

OCT 02 1991

FIGURES INDICATE BOTTOM OF FORMATION

0	-----	211	Surface
211	-----	362	Shale
362	-----	650	Shale & Lime
650	-----	921	Shale
921	-----	1835	Shale & Lime
1835	-----	1966	Shale
1966	-----	2040	Lime & Shale
2040	-----	2178	Shale
2178	-----	2339	Shale & Lime
2339	-----	2440	Lansing
2440	-----	2521	KC Lime
2521	-----	2587	Lime
2587	-----	2715	KC Lime
2715	-----	2717	Bas K.C.
2717	-----	2750	Lime
2750	-----	2795	Lime & Shale
2795	-----	2840	Lime Pawnee
2840	-----	2873	Shale & Lime
2873	-----	2925	Lime
2925	-----	2935	Shale & Lime
2935	-----	2959	Miss Chert
2959	-----	3100	Miss
3100	-----	3130	Lime Miss
3130	-----	3146	Miss
3146	-----	3159	Lime
3159	-----	3200	Lime
3200	-----	3206	Hunton Lime
3206	-----	3295	Lime
3295	-----	3329	Viola
3329	-----	3335	Simpson Sand
3335	-----	3400	Simpson
3400	-----	3420	Arbuckle RTD

REGISTRATION DIVISION  
Wichita Kansas