

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED 4-9-70
STATE CORPORATION COMMISSION
APR 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drlg. Co. Inc.

Complete Address 905 Century Plaza Wichita, Ks 67202

Lease Name Lucas Well No. 1

Location NE/NE/SE Sec. 4 Twp. 24 Rge. 15 (E) (W)

County Stafford Total Depth 4135

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 5:00PM Day 7 Month 4 Year 1970

The above well was plugged as follows:

210 ft of 8 5/8 surface pipe circulated with 175 sacks cement.

4120 ft 5 1/2 long string set with 800 gals. Latex. Plug back to 3904 ft.

Top perf. 3797 ft. Sand back to 3780 ft, 5 sacks cement with bailer.

Pulled 2583 ft of 5 1/2. Set over night bridge at 200 ft. with 10 gals.

sand, 10 sacks cement, 1 sack C.C. Plugged with 15 sacks cement,

10 ft rock bridge at 30 ft, 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: J. Russell Silvertan
Well Plugging Supervisor

DATE 4/9/70

INV. NO. 1696-W