

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1971
CONSERVATION DIVISION
Wichita, Kansas
3-29-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Wilkinson Drlg. Inc. & Midwestern Supply Co. Inc.

Complete Address 207 Brown Bldg. Wichita, Ks

Lease Name Harkness Well No. 3

Location SE/NW/NW Sec. 11 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4180

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 10:00 AM Day 26 Month 3 Year 1971

The above well was plugged as follows:

230 ft of 8 5/8 surface pipe cemented with 200 sacks. 4145 ft of 5 1/2
long string cemented with 125. sacks. Top perf. 3750.ft. Sand back
to 3700 ft, 5 sacks cement with bailer. Squeezed well with 45 sacks
cement. Pulled 285 ft of 5 1/2. Pumped 2 sacks hulls, 15 sacks gel.,
100 sacks cement to surface.

Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Siker
Well Plugging Supervisor

DATE 3/31/71

INV. NO. 3475-W