

15-095-20,003-0000

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSIONJAN 24 1967  
1-24-67  
CONSERVATION DIVISION  
WICHITA, KANSASJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasIntent to Drill, filed  
January 12, 1967Operator's Full Name Wrico  
Wrico Drilling CompanyComplete Address: 6631 East Kellogg, Wichita, KansasLease Name Young Well No. # 2Location NE NE NW Sec. 29 Twp. 27 Rge. 5 (E) (W) WCounty Kingman Total Depth 2500'Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XOther well as hereafter indicated:     Plugging Contractor: H-30 Drilling, Inc.Address: 200 North Main, Wichita, Kansas License No.     Operation Completed: Hour 8:30PM Day 20th Month Jan. Year 1967

The Above well was plugged as follows:

207' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged  
with 1 sack of cement and 1/2 sack of hulls on fluid at 200', and cemented  
with 24 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

INV. NO.

Signed: Archie Elving

Well Plugging Supervisor