

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-015-20287-00-00  
API NUMBER 10/7/69 drilled  
LEASE NAME SMITH W

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
\_\_\_\_\_ Ft. from S Section Line  
NW NW NE Ft. from E Section Line

LEASE OPERATOR FLOWERS PRODUCTION CO., INC.  
ADDRESS P.O. BOX 249, EL DORADO, KS. 67042  
PHONE# (316) 321 0550 OPERATORS LICENSE NO. 6407

SEC. 7 TWP. 27S RGE. 8 (E) ~~XXX~~  
COUNTY Butler

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 10/7/69  
Plugging Commenced 02/22/95  
Plugging Completed 02/24/95

The plugging proposal was approved on 02/24/95 (date)  
by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? no

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2736'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	200'	
				5 1/2"	2728'	607'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged back with gravel from 2725' to 2675'. Mix & dump 6 sacks cement @ 2675'. Dug cellar. Could not rip 5 1/2" csg. Subterranean log shot 5 1/2" csg @ 607'. Pulled 607' csg. Put rock bridge 290' to 270'. Bail hole dry to 270'. Had 4 1/2 yds slurry mix cement put from 270' to surface.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DALE WILSON d/b/a W. W. DRILLING License No. 6012  
Address RR #3 Box 66, El Dorado, Kansas 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dallas Flowers

STATE OF Kansas COUNTY OF Butler, ss.


Dale Wilson, plugging contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) RR #3 Box 66, El Dorado, Ks 67042

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 95

My Commission Expires:



Emma K. Utermoehlen  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 0 3 1995  
CONSERVATION DIVISION  
WICHITA