

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21,640 0000

LEASE NAME Endicott "B"

WELL NUMBER 1

1650 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 23TWP. 27RGE. 6 ~~xx~~ or (W)

COUNTY Kingman

Date Well Completed 11-5-90

Plugging Commenced 11-5-90

Plugging Completed 11-5-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TOMKAT, LTD.

ADDRESS P.O. Box 1471 Great Bend, KS 67530

PHONE#(316) 792-6960 OPERATORS LICENSE NO. 5538

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-1-90 (date)

by Don Thompson (KCC District Agent's Name).

to be filed

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4110

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 800' w/35 sacks cement thru drill pipe

Next Plug: @ 450' w/35 " " " " " 10 sacs in rat hole

Next Plug: @ 360' w/35 " " " " " 10 sacks in mouse hole

Top Plug: @ 60' w/25 " " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. RECEIVED 5884

STATE CORPORATION COMMISSION

Address P.O. Box 877 Great Bend, KS 67530 11-14-1990

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TOMKAT, LTD. NOV 14 1990

STATE OF Kansas COUNTY OF Barton, ss. CONSERVATION DIVISION

Wichita, Kansas

Ervin Neighbors

(Employee of Operator) or ~~Representative~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 90

Dorothy Intoque
Notary Public

My Commission Expires: 5-29-94

DRILLER'S WELL LOG

DATE COMMENCED: October 27, 1990
DATE COMPLETED: November 5, 1990

TOMKAT, LTD.
ENDICOTT 'B' #1
C S/2 N/2 SE
Sec. 23, T27s, R6W
Kingman County, Ks.

0 - 505' Surface Soil, Sand, Shale
505 - 1205' Shale w/lime streak
1205 - 2340' Shale & Lime
2340 - 3440' Lime & Shale
3440 - 3660' Lime
3660 - 4110' Shale & Lime
4110' RTD

ELEVATION: 1462 K.B.

Surface Pipe: Set new
8-58/8", 20# pipe @316'
w/175 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON)ss

Ervin Neighbors of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 5th day of November 1990.



Dorothy M. Macue
Notary Public

RECEIVED
NATIONAL COMMISSION
NOV 14 1990

CONSERVATION DIVISION
Wichita, Kansas