

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 25 Twp. 27 Rge. 6 (E) W (W)

Location as "NE/CNW4SW4" or footage from lines SE SE SE

Lease Owner Ken-Mar Oil Company

Lease Name Wimer Well No. 1

Office Address 709 Union National Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed April 11 19 58

Application for plugging filed April 11 19 58

Application for plugging approved April 11 19 58

Plugging commenced April 11 19 58

Plugging completed April 11 19 58

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hemper

Producing formation Depth to top Bottom Total Depth of Well 4321 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	251'	8 5/8"	251'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240' and set plug.
Cemented with 20 sacks cement.
Set top plug at 20' and cemented with 10 sacks cement.
Completed plugging at 2:00 a.m. April 11, 1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor S & S Drilling Company
Address Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. D. Sweetman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. D. Sweetman
Box 194 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of April, 19 58

Virgil E. Belford, Jr. Notary Public.

My commission expires April 27, 1961

RECORDED
STATE CORPORATION COMMISSION
APR 18 1958
04-18-58
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 25 T. 27 R. 6 W
BOOK PAGE 94 LINE 13

15095-00437-000

WELL LOG
Wimer # 1
SE SE SE 25-27S-6W
Kingman County, Kansas

0 - 251	Surface clay, red bed & shale	Elevation	1442'KB 1439'DF
251 - 485	Blue shale and shells		
485 - 1000	Shale and shells		
1000 - 1730	Lime and shale		
1730 - 1875	Shale and lime	<u>Top of Formation:</u>	
1875 - 2310	Lime and shale	Heebner	2823'
2310 - 2450	Shale and lime	Mississippi	3750'
2450 - 2935	Lime and shale	Kinder.	4037'
2935 - 2980	Sandy lime and shale	Viola	4143'
2980 - 3025	Lime and shale	Simpson	4162'
3025 - 3075	Sandy lime and shale	Arbuckle	4290'
3075 - 3475	Lime		
3475 - 3515	Lime and shale		
3515 - 3555	Shale		
3555 - 3690	Lime and shale		
3690 - 3766	Lime and chert		
3766 - 3790	Lime and shale		
3790 - 3835	Shale		
3835 - 3925	Lime and shale		
3925 - 3985	Shale and lime		
3985 - 4010	Lime		
4010 - 4028	Lime and shale		
4028 - 4143	Shale and lime		
4143 - 4158	Viola		
4158 - 4290	Simpson shale		
4290 - 4321	Arbuckle		
4321 -	T. D.		

STATE OF KANSAS

COUNTY OF BARTON ss

T. D. Sweetman, partner of S & S Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman

T. D. Sweetman

Subscribed and sworn before me this 16th day of April, 1958.

Virgil E. Belford, Jr.

Virgil E. Belford, Jr.
Notary Public, Barton County

My Commission expires April 27, 1961.

PLUGGING
FILE SEC 25-27 R 6W
BOOK PAGE 94 LINE 13