

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 31 Twp. 27S Rge. 6W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Tomlinson-Kathol

Lease Name Endicott Well No. 1

Office Address 1125 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry & Abandoned

Date well completed 6/8/ 1964

Application for plugging filed 6/8/ 1964

Application for plugging approved 6/8/ 1964


Plugging commenced 6/8/ 1964

Plugging completed 6/8/ 1964

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Elving

Producing formation None Depth to top Bottom Total Depth of Well 4284 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		Surf.	267'	8-5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud was introduced into the hole from total depth to 250 feet where the bottom plug was set and cemented with 250 sacks cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 10 sacks cement. Two sacks cement were put in the rat hole, surface pipe was cut off below ground level and the location abandoned.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 16 1964

Name of Plugging Contractor Tomlinson-Kathol (If additional description is necessary, use BACK of this sheet)  
Address 1125 Wichita Plaza, Wichita, Kansas  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Richard G. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
1125 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 64

My commission expires 1/19/65  
Esther Lamone Notary Public.

15-095-00468-0000

DRILLERS LOG  
TOMLINSON & KATHOL  
# 1 ENDICOTT  
NE NW SE, SEC. 31-27S-6W  
KINGMAN COUNTY, KANSAS


Contractor - Tomlinson & Kathol

Commenced: 5/25/65  
Completed: 6/8/64  
Elevation: 1571 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	267	Surface Hole	
267	1534	Shale & Shells	
1534	3284	Shale	267' 8-5/8" Surface Casing
3284	3354	Shale & Brown Lime	w/250 sacks
3354	3590	Lime	
3590	3702	Lime & Shale	
3702	3906	Shale & Lime	
3906	3969	Lime & Shale	
3969	4090	Mississippian	
4090	4175	Chert	
4175	4225	Chert & Shale	
4225	4251	Shale	
4251	4258	Shale, Sand	
4258	4284	Shale & Lime	
4284		Lime w/shale	
4284		Rotary Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1964  
CONSERVATION DIVISION  
Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

  
Richard C. Davis

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 12th day of June, 1964.

  
Notary Public

My Commission Expires: 1/19/65