

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-095-20966-000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 34 Twp. 27S Rge. 6 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW SE

Lease Owner Graves Drilling Co., Inc.
Lease Name Gerber Well No. 1
Office Address 910 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed June 17, 19 80
Application for plugging filed June 17, 19 80
Application for plugging approved June 17, 19 80
Plugging commenced June 17, 19 80
Plugging completed June 17, 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4335'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	201'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 40 sacks cement through drill pipe to 210'. Pushed plug & 1/2 sack huls to 40' with 10 sacks cement. Plugged rat hole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 7 1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Betty Brandt (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Betty Brandt

910 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 1980

Rebecca L. Matthews

Rebecca L. Matthews

Notary Public.

My commission expires May 17, 1983

15095-20966-0000

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: June 8, 1980
 910 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: June 17, 1980
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 201' of used 8-5/8" LOCATION: Gerber No. 1
 cemented with 185 sacks. C SW SE
 Section 34-27S-6W
 Kingman County, Kansas

0 - 201 Red bed
 201 - 1294 Red bed & shale
 1294 - 2336 Shale & lime
 2336 - 2406 Lime & shale
 2406 - 2995 Shale & lime
 2995 - 3150 Shale, lime & sand
 3150 - 3278 Shale & lime
 3278 - 3595 Lime & shale
 3595 - 3678 Shale & lime
 3678 - 3859 Lime & shale
 3859 - 3880 Shale & chert
 3880 - 4045 Lime
 4045 - 4178 Shale & lime
 4178 - 4275 Lime & shale
 4275 - 4335 Shale & lime
 4335 Rotary Total Depth

Copy sent to:

State Corporation Commission
 Kansas Geological Survey
 Kansas Geological Society

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 7 1980
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Rebecca L. Matthews
 Secretary-Treasurer

STATE OF KANSAS)
) ss.
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 3rd day of July, 1980.

Rebecca L. Matthews Notary Public

My commission expires: May 17, 1983