

API NUMBER 15-151-10235-0001

LEASE NAME S.I.C.U. (Justice)

WELL NUMBER #19

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

900 Ft. from S Line of Section (circle one)

330 Ft. from E Line of Section (circle one)

LEASE OPERATOR I/C Development L.L.C.

SPOT LOCATION NW. SW. SW.

ADDRESS Box 847

SEC. 18 TWP. 27 S. RGE 12W (S) or (W)

CITY, STATE, ZIP Pratt, KS 67124

COUNTY Pratt

PHONE#(316) 672-2531 OPERATORS LICENSE NO. 31739

Date Well Completed June 1953

Character of Well ENHR
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced Sept. 25, 1998

Date Plugging Completed Sept. 28, 1998

The plugging proposal was approved on May 7, 1997 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? ✓ If not, is well log attached?

Producing Formation(s) Simpson Depth to Top PBTD 4359 Bottom 4359 T.D. 4363'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Perf. 4222' to 4334' 4344' to 4353' 4292' to 4313' CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULL OUT |
|-----------|----------------|------|-------|--------|--------|----------|
| | Surface Casing | 0 | 768' | 8 5/8" | 768' | 0 |
| | Prod. Casing | 0 | 4363' | 5 1/2" | 4363' | 1850' |
| | | | | | | |
| | | | | | | |

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Shot Casing OFF at 1850'
Set CIBP at 4222' w/ 2 sxs. Cement. Ran 2 1/2" Tubing to 805', and
pumped 40 bbls drlg. mud, then 50 sxs. Cement w/ 3% CC. Pulled up to
310', pumped 40 sxs cement, pulled to approx. 61', pumped 20-25 sxs.
cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: I/C Development L.L.C.

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart / OFFICE Manager (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) c/o Pratt Well Service Inc

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1998

Kenneth W. Furgason
Notary Public

My Commission Expires: 06/19/00

