



15095-00468000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Boman of Tomlinson & Kathol has this

date requested permission to plug the following described well:

Mr. Boman guarantees payment of the plugging fee.

Operator's full Name: Tomlinson & Kathol

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: Endicott Well No. # 1

Location: NE NW SE Sec. 31 Twp. 27 Rge. 6 (E) (W) W

County Kingman Total Depth 4284 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Boman was instructed to plug the well as follows:

267' of 8 5/8" surface pipe, cemented with 200 sacks. Fill  
hole with drilling mud to 250', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent