

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 16 1964  
3-16-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Warren Davis of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Hellar Drilling Co., Inc.

Complete Address: 1014 Union Center, Wichita, Kansas

Lease Name: Birdsall Well No. # 1

Location: App. E/2 NW NW Sec. 9 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4180 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

231' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole with drilling mud to 225'; 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent