

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONOCT 16 1972
10-16-72
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herren of H-30 Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.Operator's full Name: Kathol Petroleum Inc.Complete Address: 900 Sutton Place Wichita, KsLease Name: Petro Well No. 1Location: NE/SW/NE Sec. 9 Twp. 24s Rge. 15 (E)(W) WCounty: Stafford Total Depth 4078 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Herren was instructed to plug the well as follows:

346 ft 8 5/8 surface pipe cemented with 250 sacks; Pump
40 sacks cement to 650 ft. 2nd plug at 300 ft with 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent