

State of Kansas



15-095-20,003-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1967  
1-24-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill, filed  
January 12, 1967

Dear Sir:

Mr. Howard Panteratz of H-30 Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Panteratz guarantees payment of the plugging fee.

Operator's full Name: WRICO  
Wireco Drilling Company

Complete Address: 6631 East Kellogg, Wichita, Kansas

Lease Name: Young Well No. # 2

Location: NE NE NW Sec. 29 Twp. 27 Rge. 5 (E)(W) W

County Kingman Total Depth 2500' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Panteratz was instructed to plug the well as follows:

207' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill  
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent