



59

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
July 11, 1970

JUL 17 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-079-19049-0000

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Glen of Pipe Pullers, Inc. has this
date requested permission to plug the following described well:

Mr. Glen guarantees payment of the plugging fee.

Operator's full Name: Homestake Production Company

Complete Address: Box 68, Burrton, Kansas 67020

Lease Name: Martindale Well No. W-31

Location: SW NW SE Sec. 18 Twp. 23 Rge. 3 (E)(W) X

County: Harvey Total Depth 3369' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Glen was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks cement.

Fill hole with mud to 225'. Set rock bridge from 225' to 200' and

cement hole to base of cellar with 4 yards ready-mix concrete.

Very truly yours,

Conservation Division Agent