

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM

15-079-00534-0000 (PLEASE TYPE FORM and File ONE Copy)

API # Spud 11/7/48 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *6/95*

WELL OPERATOR Kaiser-Francis Oil Company KCC LICENSE # 6568
(owner/company name) (operator's)

ADDRESS P. O. Box 21468 CITY Tulsa

STATE OK ZIP CODE 74121-1468 CONTACT PHONE # (918) 491-4314

LEASE Wiley WELL# 4 SEC. 18 T. 23S R. 3 (~~East~~/West)

- NW - NE - NE SPOT LOCATION/QQQQ COUNTY Harvey

4950 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM (E) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 275 CEMENTED WITH 275 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3312 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open hole from 3312'-3360'

ELEVATION 1473 T.D. 3360 PBD 3360 ANHYDRITE DEPTH n/a
(~~Est.~~/K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 3270' w/2 sxs cmt on top. Fill hole with mud.
Locate free point. Shoot off casing. Spot cmt plug 100' in and out of 5 1/2" casing stub.

Set cmt plug in surface casing. Set cmt plug from 30' to surface.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? On old form
If not explain why? We cannot locate a file for this well

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John Glenn PHONE# (316) 564-3214

ADDRESS 515 E. 3rd City/State Ellinwood, KS 67526

PLUGGING CONTRACTOR Kelso Casing Pulling KCC LICENSE # 8059
(company name) (contractor's)

ADDRESS Box 347, Chase, KS 67524 PHONE # (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) To be scheduled upon approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/16/94 AUTHORIZED OPERATOR/AGENT: C. Jan Valkenburg
(signature)

Charlotte Van Valkenburg

6/95
RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1994



Kansas Corporation Commission

Joan Finney, Governor Susan M. Selesam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 22, 1994

Kaiser-Francis Oil Company
P O Box 21468
Tulsa OK 74121-1468

Wiley #4
API 15-N/A
4950 FSL 990 FEL
Sec. 18-23S-03W
Harvey County

15-079-66534-0000

Dear John Glenn,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2
202 W. First, Suite 304
Wichita KS 67202
(316) 263-8809

William R. Bryson, Director Conservation Division
KCC, Conservation Division, Wichita State Office Building
130 S. Market, Room 2078, Wichita, Kansas 67202 (316) 337-6200