

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-20367-0000

245 North Water  
Wichita, KS 67202

Operator's Full Name Tom Schrag

Complete Address R. R. # 2 Burrton, Ks. 67020

Lease Name Schrag Well No. # 1

Location SW. NW. NE. Sec. 10 Twp. 23 - Rge. 3 (~~East~~) (West)

County Harvey Total Depth 3366'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. # 683

Operation Completed: Hour: 6:15 PM Day: 6 Month: 11 Year: 1980

The above well was plugged as follows:

8 5/8" sur. csg. 272' circ/cemt. 4 1/2" csg. 3364'/75 sx. cemt.

Perf. 3314' to 3318', Perf. 3270' to 3278'. Allied Cementing pumped  
35 sx. cemt., 1 sx. hulls. to 3000', shut in let set.

Shot & pulled 2855' of 4 1/2" csg. Left 509' csg. in hole.

Allied Cementing Pumped down 8 5/8" csg. 4 sx. hulls, 20 sx. gel.,

2 sx. hulls, plug, 135 sx. cemt. 50/50 posmix + 4% gel.

Pump Press. 300# S. I. P. 150# Shut well in.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1980  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

I hereby certify that the above well was plugged as herein stated

DATE 11-18-80 Signed: Alon Thompson  
INV. NO. 8140-E Conservation Division Agent