

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 138-7

LOCATION Sw-NW-SE

SEC. 20 TWP. 19 RGE. 12

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Welsh
Oil Capital Corp. Operator Lewis Ind. Co. Address 607 un. Nat. Bk. Bldg
Wichita, Kansas
Field _____ County Barton

Total Depth 3475 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 205' c.w.c. 5 1/2" casing
set 3458' w/ 125 ss cem. P.B. 32.66' top perf
3252'. Sand to 3248' dump 5 ss cem.
Shot off and pulled 5 1/2" casing. Filled
hole with heavy mud to 225' set
rock bridge and dumped 20 ss cem. mud to
35' rock bridge and 10 ss cem. to base of cellar

Warren H. Horner
District Conservation Agent

Date July 29, 1955

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 X 1955
08-01-55
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 20 T 19 R 12N
BOOK PAGE 138 LINE 7

144-44