

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

#2

15-079-20377-0000

API NUMBER Sept 8-1978

LEASE NAME Goodyear #1

WELL NUMBER 1

SPOT LOCATION NW NW SW

SEC. 10 TWP. 23 RGE. 3W (E) or (W)

COUNTY Harvey

Date Well Completed 9-8-78

Plugging Commenced 12-11-85

Plugging Completed 12-13-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Harold J Milburn

ADDRESS 7315 N Monroe Hutchinson KS 67502

PHONE # (816) 663-1616 OPERATORS LICENSE NO. 5526

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? KCC

Is ACO-1 filed? yes If not, is well log attached? NA

Producing formation Miss Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	335'	8 3/8	335	0
	prod casg	0	3288	4 1/2	3288	1470'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plug bottom from 3295 to 3200' w/sand. Dumped 4 sacks cement w/ Dump trailer. Shot pipe @ 2000' 1500'; 1470' pulled casing. Built wood & rock bridge @ 400' filled from 400' to surface w/ 7yds Redi-Mix

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Grossel Oil Field Service License No. 5823  
Address Box 286 Burrton KS 67020

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, SS.

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.




MAR 31 1986  
3-31-86  
CONSERVATION DIVISION  
WICHITA, KANSAS

(Signature) Ed Grossel  
(Address) Box 286 Burrton KS 67020

SUBSCRIBED AND SWORN TO before me this 17<sup>th</sup> day of December, 1985

My Commission expires: March 15, 1989

Mary H. Klein  
Notary Public



# Blackstone Drilling, Inc.

Box 2184 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

15.074-2037-0000

September 8, 1978

COMPANY: HAROLD J. MILBURN  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: GOODYEAR #1  
 LOCATION: NW NW SW Section 10-23-3W,  
Harvey County, Kansas  
 COMMENCED: August 30, 1978  
 COMPLETED: September 8, 1978  
 ELEVATION: Est. 1478 K. B.

0	to	300	Sand
300	to	346	Blue Shale
346	to	1740	Shale & Lime
1740	to	2085	Lime
2085	to	2530	Shale & Lime
2530	to	3187	Lime
3187	to	3262	Shale & Lime
3262	to	3294	Mississippi
		3294	T. D.

Cut 12 1/2" hole to 333' and run 335' of 8 5/8" surface pipe, cemented with 275 sacks of cement at 333'. Plug down at 1:15 P. M., August 30, 1978. Cut 7 7/8" hole to 3294'. Run 3297' of 4 1/2" pipe casing, cemented 6' off bottom at 3288' with 75 sacks of cement. Plug down at 5:15 A. M., September 8, 1978.

TOPS: LANSING - 2545'                      MISSISSIPPI - 3262'


Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is true and correct copy of log on your Goodyear #1, located on the NW NW SW Section 10-23-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 11 day of September, 1978.

  
Johnnie L. Schmidt - Notary Public

STATE NOTARY PUBLIC  
 JOHNIE L. SCHMIDT  
 McPherson County, Kansas  
 My Appt. Exp. June 23, 1981

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 7 1978

CONSERVATION DIVISION  
 Wichita, Kansas