


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas



Locate well correctly on above Section Plat

Reno County, Sec. 11 Twp. 23S Rge. 4 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE NW  
Lease Owner Sunray Oil Corporation  
Lease Name Sabin Well No. A-2  
Office Address Box 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 4/23 19 35  
Application for plugging filed 6/1 19 51  
Application for plugging approved 6/4 19 51  
Plugging commenced 6/18 19 51  
Plugging completed 6/26 19 51  
Reason for abandonment of well or producing formation Non-Profitable  
If a producing well is abandoned, date of last production August, 1947 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. Durkee  
Producing formation Hunton Depth to top 3609' Bottom 3621' Total Depth of Well 3621 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Hunton Lime	Oil	3609'	3621'	8-5/8" 13"		3221' 120'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3287'. Rocked hole to 3300' and ran 8 sax of cement. Mudded hole to 320', set 20' rock bridge and ran 25 sax of cement. Mudded hole to 12' and ran 10 sax of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 7 1951

CONSERVATION DIVISION  
Wichita, Kansas

7-7-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation  
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. E. Westbrook, Jr. (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.  
Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of July, 19 51

Martha Scott  
Notary Public.

My commission expires April 19, 1952.

PLUGGING  
NE SEC 11 T 23 R 4W  
BOOK PAGE 85 LINE 38

Sunray Oil Corporation, #2 SABIN 'A'  
 990' N & 330' W of SE Cor of NW/4  
 Section 11-23S-4W  
 Reno County, Kansas

15-155-62763-0000

DRILLING LOG:

Sand	0	190
Red bed	190	260
Sand & shells	260	327
Shale & shells	327	720
Lime & shale	720	853
Shale & shells	853	1985
Lime	1985	2074
Broken lime	2074	2145
Shale & shells	2145	2225
Lime & shale	2225	2340
Sandy shale	2340	2495
Shale & shells	2495	2535
Sand	2535	2535
Lime & shale	2535	2632
Lime	2632	2675
Shale & shells	2675	2780
Shale & lime	2780	2835
Lime	2835	3050
Shale & shells	3050	3100
Shale & shells	3100	3145
Broken lime	3145	3180
Shale	3180	3202
Brown shale	3202	3255
Chat	3255	3430
Lime	3430	3455
Shale	3455	3580
Black Shale	3580	3587
Grey shale	3587	3590

TD - DF 3621'

I, the undersigned, do hereby certify that the above is a true and correct well log of the above described well to the best of my knowledge.

*W. E. Westbrook, Jr.*

Subscribed and sworn to before me this 6th day of July, 1951.

RECEIVED  
 CONSERVATION COMMISSION

**PLUGGING**  
 REC SEC 11 T 23 S 4 W  
 BOOK PAGE 85 LINE 37

JUL - 7 1951

CONSERVATION COMMISSION  
 Notary Public  
*Martha Scott*

My Commission Expires: April 19, 1952.