

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas


WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Reno

County. Sec. 11 Twp. 23S Rge. 4 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ of SE $\frac{1}{4}$ of SE $\frac{1}{4}$

Lease Owner. Barnsdall Oil Co

Lease Name. M. Sabin

Well No. C-8

Office Address. Box 2039, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date, well completed. Feb. 13th, 1940 1935

Application for plugging filed. March 1st, 1940 193

Application for plugging approved. Feb. 28th, 1940 193

Plugging Commenced. Feb. 21st, 1940 193

Plugging Completed. March 10th, 1940 193

Reason for abandonment of well or producing formation. Not producing in
Paying Quantities

If a producing well is abandoned, date of last production. March 9th, 1937 193

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes - Verbal

Name of Conservation Agent who supervised plugging of this well. Mr. Ruel Durkee, Lyons, Kans

Producing formation. Hunton Depth to top. 3588 Bottom. 3607 Total Depth of Well. 3607 Feet

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Chat	Oil & Gas	3258	3500	16" OD	143.64'	None
Hunton Lime	Oil	3588	3607	13" OD	594.08'	None
				8 5/8" OD	3585.03'	3184' 4"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with rotary mud from 3607 to 3580'; - 10 Sacks cement from 3580' to 3548';
filled with rotary mud from 3548' to 3250'; 10 sacks cement from 3250' to 3215';
filled with rotary mud from 3215' to 250'; 15 sacks cement from 250' to 230'; filled
to surface with rotary mud with 5 sack cement cap.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. The Barnsdall Oil Co.

Address. Box 2039, Tulsa, Okla

STATE OF KANSAS, COUNTY OF RENO, ss.

H. H. Echols (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. H. Echols Dist. Supt.

Box 396, Burrton, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 13th day of March 1940, 19

My commission expires. Feb. 16th, 1941



Notary Public.

BARNSDALL OIL COMPANY
 MARTHA SABIN WELL NO. C-8

15-155-02785-0000

Located: 330' North & 990' West of SE Corner Drilling Comm: 1-16-35
 of lease, Section 11-23S-4W, Reno County, Kans Drilling Comp: 2-13-35

INITIAL PRODUCTION: Pumped 1107 Bbls/24 hrs (2-16-35)

CASING RECORD:

16" OD 70#	8 thd	LW	7 Jts.	143.64'	Set at 151.00' with 200 Sacks
13" OD 50#	8 thd	LW	29 Jts.	594.08'	Set at 595.69' with 250 Sacks
8 5/8" OD 28#	8 thd	SS	122 Jts.	3585.03'	Set at 3589.00' with 100 Sacks

FORMATION RECORD:

Soft sand	0	135	
Shale, hard	135	151	Set 16" OD Casing at 151'
Red Bed	151	255	
Salt & Shells	255	570	
Lime	570	738	Set 13" OD Casing at 594.08'
Shale & Shells	738	1100	
Lime & Shale	1100	1258	
Shale & Shells	1258	1755	
Shale	1755	1821	
Shale & Shells	1821	2045	
Shale	2045	2102	
Shale & Shells	2102	2210	
Shale	2210	2265	
Lime & Shale	2265	2332	
Shale & Shells	2332	2390	
Shale	2390	2430	
Sandy shale & Shells	2430	2535	
Lime	2535	2595	
Shale & Shells	2595	2660	
Lime	2660	2670	
Sand	2670	2700	
Lime	2700	2705	
Sand	2705	2745	
Lime	2745	2755	
Shale	2755	2760	
Lime	2760	2765	
Broken lime	2765	2855	
Lime	2855	2905	
Lime & Shale	2905	2985	
Lime	2985	3035	
Shale & Shells	3035	3130	
Shale	3130	3270	
Chat	3270	3430	
Lime	3430	3444	
Chat	3444	3450	
Lime	3450	3495	
Shale	3495	3589	
Hunton Lime	3589	3604	Set 8 5/8" Casing at 3589'
Sylvan Shale	3604	3607	Total Depth

