

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mall or Del Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford

County. Sec. 1 Twp. 24 Rge. 11 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-E/2 NW NW

Lease Owner Sunray Oil Corporation

Lease Name McNickle Well No. 5

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-24-45 19

Application for plugging filed 6-13-51 19

Application for plugging approved 6-14-51 19


Plugging commenced 6-29-51 19

Plugging completed 7-3-51 19

Reason for abandonment of well or producing formation Stopped producing

If a producing well is abandoned, date of last production June 19, 1951 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Viola Depth to top 3721 Bottom Total Depth of Well 3736 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Misner		3686'	3691'	5-1/2"	3722	3019
Shale		3691	3699			
Sand	Odor	3699	3703			
Viola	Oil	3721	3736			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3736-3710 & ran 5 sax of cement. Checked fluid to 100'. Bailed hole to 250. Set plug & rocked hole to 235' & ran 15 sax cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sax cement.

7-14-51

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. E. Westbrook, Jr. (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of July, 1951

Martha Scott
Notary Public.

My commission expires April 19, 1952.

PLUGGING
FILE SEC 1 T24 R1W
BOOK PAGE 88 LINE 4

Sunray Oil Corp., #5 McNickle
Section 1-24-11, Stafford Co., Kansas

WELL LOG

<u>Formation</u>	<u>Depth</u>
Sand & surface clay	165'
Red rock	300
Red bed	332
Red rock & shale	500
Red rock & shale	965
Shale & shells	1350
Broken lime	1395
Lime & shells & shale	1495
Shale & lime	1650
Lime & shale & shells	1730
Lime	1770
Shale & lime	2365
Broken lime	2455
Shale & lime	2575
Broken lime	2660
Shale	2730
Lime	2790
Shale	2825
Lime & shale	2880
Lime	2925
Shale & lime	3015
Lime	3145
Lime & shale	3170
Lime	3195
Shale gray	3225
Lime	3245
Broken lime	3305
Shale & lime	3345
Lime	3400
Lime & chert spots	3435
Chert	3455
Lime	3610
Lime & shale	3650
Lime & shale	3695
Lime & sand	3706
Shale	3721
Lime	3724
Lime & chert (sl. sat.)	3725 $\frac{1}{2}$
Lime & chert, (Hard)	3727
Hard lime	3729 $\frac{1}{2}$
Lime, good show of gas	3732
Cherty Dolomite	3736 $\frac{1}{2}$

6-14-51

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1951

CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, do hereby certify that the above is a true and correct well log of Sunray Oil Corporation's McNickle Well #5 located Sec. 1-24-11, Stafford County, Kansas.

R.C. McMahon

Engineer

Subscribed and sworn to before me this 13th day of June, 1951.

Martha Scott

Notary Public

My Commission Expires: April 19, 1952.

