


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 1 Twp. 24 Rge. 08E 11 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines C-E/2 NE NW
Lease Owner Sunray Oil Corporation
Lease Name McNickle Well No. 4
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Aug. 13 19 53
Application for plugging filed June 13 19 51
Application for plugging approved June 14 19 51
Plugging commenced July 5 19 51
Plugging completed July 14 19 51
Reason for abandonment of well or producing formation Non-profitable
If a producing well is abandoned, date of last production June 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Viola Depth to top 3702 Bottom 3706 Total Depth of Well 3734 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-------------|-------------|------|------|--------|--------|------------|
| Misner Sand | Strong Odor | 3678 | 3681 | 5-1/2" | 3704' | 2514' |
| Viola Lime | Oil | 3702 | 3706 | 8-5/8" | 330' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 3734' to 3700' & ran 5 sax of cement. Pumped plug to 2950'. Bailed hole to 250' & mudded hole to 250'. Set rock bridge to 240' & ran 15 sax of cement. Mudded hole to 35', set rock bridge to 28' & ran 10 sax of cement on top.

RECEIVED
STAFFORD COUNTY
JUL 25 1951
CONSERVATION DIVISION
WICHITA, KANSAS
7-25-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. E. Westbrook, Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of July 19 51

My commission expires April 19, 1951

Notary Public
JUL 25 1951

22-7377-s 4-49-10M
PLUGGING
FILE SEP 1 24 1951
CORR PAGE 88 LINE 3

Sunray Oil Corporation #4 McNickle
Sec. 1-24-11, Stafford County, Kansas

WELL LOG

| <u>Formation</u> | <u>Depth</u> |
|--|--------------|
| Sand | 165' |
| Red rock | 330 |
| Red rock & shells | 495 |
| Anhydrite | 520 |
| Shale & shells | 1235 |
| Salt & shells | 1285 |
| Broken lime | 1658 |
| Lime | 1710 |
| Broken lime | 1770 |
| Lime & shale | 1890 |
| Shale & lime & shells | 1995 |
| Broken lime | 2087 |
| Shale & shells | 2245 |
| Broken lime | 2430 |
| Lime | 2485 |
| Broken lime | 2820 |
| Lime & shale | 2835 |
| Shale & shells | 2866 |
| Lime | 2925 |
| Topeka lime | 2995 |
| Lime | 3165 |
| Lime & shale | 3250 |
| Shale | 3310 |
| Shale & lime | 3350 |
| Lime | 3375 |
| Lime & shale | 3450 |
| Lime | 3572 |
| Lime | 3574 |
| Lime & shale | 3670 |
| Shale & little chert | 3680 |
| Misner Sand | 3694 |
| Shale | 3708 |
| Lime hard some chert | 3718 |
| Cherty lime, hard white | 3722 |
| Cherty lime gray (1st sho of O & G) | 3724 |
| Cherty lime brown | 3726 |
| Lime & chert (little more oil) | 3732 |
| Sat. lime 35% chert Dplo | 3733 |
| Lime & chert lime hard | 3734 |

6-14-51
RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1951
CONSULTING DIVISION

I, the undersigned, do hereby certify that the above is a true & correct well log of Sunray Oil Corporation's McNickle well #4, Sec. 1-24-11, Stafford County, Kansas.

R.C. McMechan
Engineer

Subscribed and sworn to before me this 13th day of June, 1951.

Martha Scott
Notary Public

My Commission expires: April 19, 1952.

