

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Stafford County. Sec. 1 Twp. 24S Rge. (E) 11(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW NW SE
Lease Owner The Texas Company
Lease Name M. Volker Well No. 5
Office Address Box 2420, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 30 1944
Application for plugging filed November 30 1946
Application for plugging approved December 25 1946
Plugging commenced December 20 1946
Plugging completed December 24 1946
Reason for abandonment of well or producing formation Operation is unprofitable
If a producing well is abandoned, date of last production October 6 1946
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well H. W. Kerr, Gt Bend, Kansas
Producing formation Viola Depth to top 3730 Bottom 3767 $\frac{1}{2}$ Total Depth of Well 3791 $\frac{1}{2}$ Feet
Show depth and thickness of all water, oil and gas formations. Deepened To 3791'
OIL, GAS OR WATER RECORDS CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"OD	313	0
				5-1/2"OD	3712	2829

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Information: 3791' to 3687' Sand
3687' to 3682' Mud
3682' to 3632' Cement, 5 Sax
3632' to 350' Mud
350' to 200' Cement, 15 Sax
200' to 100' Mud
100' to Top Cement, 10 Sax

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Texas Company
Address 614 Bitting Bldg, Wichita, Kansas



STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell
614 Bitting Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 19 47

My commission expires 8/26/49

Bertha W. Butts
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-185-12521-0000

ALF LONDON
Maggie Volker No. 5.

SEC.1 T.24 R.11 W
1Wc SE

Total Depth. 3767 $\frac{1}{2}$ '
Comm. 5-15-43 Comp. 6-20-43
Shot or Treated.
Contractor. Campbell & Kuhn
Issued. 8-7-43

County. Stafford



CASING:
8 5/8" 323'
5" 3717'

Elevation.

Production. Pot. Est. 200 B.

Figures Indicate Bottom of Formations.

sand	0-40
red bed & shells	323
red bed	420
red bed & shale	540
shale & shells	1272
shale & lime	1419
lime brk.	1470
lime & shale	1506
lime brk.	1830
lime brkn	1918
lime brk	2070
lime brkn	2136
lime brk	2340
shale & shells	2457
lime brk	2535
lime brk & shale	2592
lime & shale	2675
lime brk	2867
lime	3313
lime brk	3365
lime	3423
chert	3426
lime	3516
lime brk	3550
lime	3709
Misener sand	3718
lime cherty	3724
shale green	3727
dol.	3730
first pay	3733
sdyl dol.	3737
lime	3747
cherty lime-best pay	3751
lime cherty-S.S.O.	3755
lime cherty-S.S.O.	3757
lime cherty-S.S.O.	3758
lime cherty-S.S.O.	3761
lime cherty-pyrite	3763
cherty dol.w/ sh oil	3767 $\frac{1}{2}$
Old Total Depth.	

Drld Deeper In
Viola To 3791' New T.D.

1 24 11W
84 23