

STATE OF KANSAS
ATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22154-00-01

LEASE NAME Zenith Unit

WELL NUMBER 24

2640 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 1 TWP. 24S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3-10-03

Plugging Completed 3-13-03

RECEIVED

MAR 21 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR ZU, LLC

ADDRESS 108 W. 34th Hays, Kansas 67601

PHONE# (785) 625-6588 OPERATORS LICENSE NO. 32699

Character of Well INJ.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3839'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	250'	None
				5-1/2"	3838'	2210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each sack.

Plugged off bottom with sand to 3480' and 5 sacks cement. Shot pipe @2200' and 2210'.
Layed down 5-1/2" casing. Plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement,
10 sacks gel, 100# hulls, released plug and 100 sacks cement. 60/40 pos, 6% gel.
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ZU, LLC

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of March, 2003

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-

[Signature]