


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 1 Twp. 24 Rge. (E) 11 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE NW SE  
Lease Owner The Derby Oil Company  
Lease Name McNickle Well No. 3  
Office Address 122 W. Douglas, Wichita, Kansas Box 1030  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed April 1 19 52  
Application for plugging filed May 2 19 52  
Application for plugging approved May 7 19 52  
Plugging commenced June 24 19 52  
Plugging completed July 1 19 52  
Reason for abandonment of well or producing formation Wells have reached their economic limit  
If a producing well is abandoned, date of last production March 19 52  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Misner & Viola Depth to top M-3712 Bottom M-3720 Total Depth of Well 3764 Feet  
Show depth and thickness of all water, oil and gas formations. V-3731 V-3764

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Misner sand	Oil	3712	3720	10"	290'	None
Viola	Oil	3731	3745	7"	3712'	2874'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 6 sacks of cement at 3705'. Shot pipe off at 2874'. Pulled pipe & judded hole to 250'. Set rock bridge & dumped 25 sacks of cement at 250'. Finished mudding hole & dumped 10 sacks of cement at top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1952  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Bert Self  
Address 119 E. 6th, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
F. W. Heiser (employee of owner) or (operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. W. Heiser*  
Assistant-to-the-President  
122 W. Douglas, Wichita, Kansas Box 1030  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of July, 19 52.

My commission expires August 24, 1953 Notary Public.



15-185-12524-0000

THE DERBY OIL COMPANY

Record of Well No. 3  
 Location Approx. SE NE NW SE  
 440' NL 1155' WE  
 Contractor E. K. Carey  
 Drilling commenced 3-1-43  
 Elevation 1809

McNickle Farm  
 Sec. 1 Twp. 24 Rge. 11 W  
 County Stafford  
 State Kansas  
 Drilling completed 4-4-43

Casing Record

Size	Feet	Kind	Weight
10"	290'	Seamless	100 sacks Halliburton Regular & 50 sacks Quick-set
7"	3712'	O. D.	24#

Formation	Bottom	Formation	Bottom
Sand	0-90	Sand & chert	3726
Red rock & shale	120	Chert & lime	3747
Sand & shale	170	Lime	3764
Red rock & shells	290		T.D. Cable tool
Red bed	480		
Anhydrite	505		
Shale & shells	985		
Shale & salt	1341		
Shale & shells	1485		
Lime	1970		
Broken lime	2267		
Shale & lime shells	2350		
Shale & lime	2470		
Shale & lime shells	2550		
Shale & lime	2730		
Shale	2825		
Lime	3212		
Sandy lime	3237		
Lime	3325		
Broken lime	3394		
Lime <del>3444</del>	3444		
Cherty lime	3460		
Lime	3528		
Chert	3535		
Lime	3582		
Lime & shale	3620		
Lime	3700		
Lime & shale	3712		
T.D. Rotary Table	3715		

GEOLOGICAL DATA

Tops:

Lansing 3360  
 Misner 3711  
 Viola dol 3731

Flowed 22 BO 3 hrs. DD Flowed 74 BO  
 3 hrs. Gave 2000 A. Flowed 30 BOPH for  
 2 hrs. thru 3/4" choke. 30' free oil  
 from 2711 to 3741. Good sat 3741-64.  
 Bomb pot. 3035

CABLE TOOL

Broken sand-little oil	3716
Brown sand	3718
Sandy lime	3720
Sand & chert-increase gas	3723

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 17 1943 7-17-52

PLUGGING DIVISION  
 STATE CORPORATION COMMISSION  
 Topeka, Kansas  
 FILE SEC-17-24-R-110  
 BOOK PAGE 19 LINE 3