


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County, Sec. 1 Twp. 24S Rge. 11 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE NW  
Lease Owner Sunray Oil Corporation  
Lease Name McNickle Well No. 3  
Office Address Box 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 30 19 43  
Application for plugging filed June 13 19 51  
Application for plugging approved June 14 19 51  
Plugging commenced June 22 19 51  
Plugging completed June 28 19 51  
Reason for abandonment of well or producing formation Non-profitable

If a producing well is abandoned, date of last production Jan. 24, 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives  
Producing formation Viola Depth to top 3723 Bottom Total Depth of Well 3747 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
KC Lime		3334		5-1/2"		2962'
Misner Sand		3700	3702			
Dolomite Lime	Oil	3726	3747			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Set plug at 2720', rocked hole to 2706' and ran 5 sax of cement. Drove plug to 2960'. Cleared hole, bailed surface pipe to 250' and set rock bridge to 238'. Ran 15 sax of cement. Mudded hole to 35', rocked to 30' and ran 10 sax of cement on top.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 5 - 1951  
7-5-51  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Sunray Oil Corporation  
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. E. Westbrook, Jr. (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.  
Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of July, 1951

Martha Scott  
Notary Public.

My commission expires April 19, 1952.

FILED  
MAY 24 1951  
BOOK PAGE 88 LINE 2

Sunray Oil Corporation  
 #3 McNickle  
 Sec. 1-24-11, Stafford Co., Kansas

## WELL LOG

<u>Formation</u>	<u>Depth</u>
Cellar	9'
Sand & clay	170
Red bed & sand	190
Sand shale, red bed	318
Red bed shale	500
Red rock shale & shells	633
Red bed	750
Shale shells & little sand	800
Shale & shells	1005
Shale & shells & salt	1158
Shale & lime	1464
Shale & lime	1564
Lime	1672
Sharp lime & shale	1862
Shale & shells	1895
Lime & shale	1948
Shale & shells	2037
Lime & shale	2222
Shale & shells	2475
Lime & shale	2591
Lime	2621
Broken Lime	2696
Lime & shale	2754
Broken lime	2918
Lime	3065
Lime & shells	3150
Broken lime	3240
Shale	3284
Lime & shale	3320
Broken lime	3379
Lime & shale	3424
Lime w/sand streaks	3472
Lime & shale	3569
Lime	3657
Lime & shale	3686
Shale sand & lime	3718
Lime & chert	3731
Lime & sl. sho of oil	3734
Lime (little more gas)	3736
Lime brown soft	3743
Lime chert	3747

JUN 14 1951

6-14-51

CONSERVATION DIVISION

Wichita, Kansas

I, the undersigned, do hereby certify that the above is a true and correct well log of Sunray Oil Corporation's McNickle well #3, Sec. 1-24-11, Stafford County, Kansas.

*R.C. McMahon*  
 Engineer

Subscribed and sworn to before me this 13th day of June, 1951.

*Martha Scott*  
 Notary Public

My commission expires: April 19, 1952.

