

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 2 Twp. 24 Rge. 11 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. CNL NE SE, 330 FNL, 660 FEL
Lease Owner: The Bay Petroleum Corporation
Lease Name: McNickle Well No. 4
Office Address: Box 957 Denver, Colorado.
Character of Well (completed as Oil, Gas or Dry Hole): Oil Well
Date well completed: 12-5 1940
Application for plugging filed: 2-11 1947
Application for plugging approved: 2-13 1947
Plugging commenced: 3-24 1947
Plugging completed: 3-25 1947
Reason for abandonment of well or producing formation: Failure to produce in quantity sufficient to warrant continued operation.
If a producing well is abandoned, date of last production: 3-23 1946
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. H.W. Kerr
Producing formation: Viola Depth to top: 3665 Bottom: 3758 Total Depth of Well: 3758 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13"	161'	None
				8 5/8"	282'	None
				5 1/2"	3732'	1790' 9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole,
Set bridge at 250'
Ran 15 sax of cement,
Mudded hole,
Ran 10 sax of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: The Bay Petroleum Corporation,
Address: Box 513, Chase, Kansas.

STATE OF Kansas, COUNTY OF Rice, ss.

_____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Lawrence Crawford*

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of April, 1947

APR - 2 1947

My commission expires May 20, 1950

PLUGGING
FILE SEC 2 T 24 R 11 W
BOOK PAGE 97 LINE 37

Notary Public.

WELL LOG BUREAU * KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

BAY PETROLEUM CORPORATION.
McNickle No. 4

Sec. 2 T. 24 R. 11W
CNL NE SE
330' FNL 660' FEL SE 1/4

Total Depth. 3758'
Comm. 12 - 5 - 40. Comp. 12 - 25 - 40.
Shot or treated. 6000 gal acid.
Contractor.
Issued. 2 - 8 - 41.

County . Stafford.

Casing.

13" 161'
8 5/8" 282'
5 1/2" 3732'

Elevation. 1802

Figures indicate bottom of formation.

clay	18	shale	2796
sand	72	lime brown	2817
clay	114	lime and shale	2860
shale shells	190	lime	2970
red rock	223	lime broken	2995
sand	228	lime	3218
shale	252	lime and shale	3355
red rock	297	lime	3402
shale shells	505	lime streaks of	
anhydrite	516	chert	3442
shale shells	1006	lime	3606
shale	1088	shale and lime	3667
salt and shale	1287	sand	3675
shale shells	1430	shale	3684
lime broken	1530	chert	3685
lime	1593	dolomite	3688
lime brown	1652	chert and lime	3754
lime and shale	1818	chert	3758
cherty lime	1838	Total Depth.	
lime	1967		
lime and shale	2033	Top Lime	3303
lime	2067	Misener	3652
lime brown	2093	Viola	3665
lime and shale	2240		
lime	2263		
shale	2277		
lime	2296		
shale	2319		
lime	2322		
shale lime	2455		
lime brown	2505		
shale lime	2599		
lime	2677		
shale	2729		
lime	2756		

APR - 2

PLUGGING
FILE SEC 2 T 24 R 11W
BOOK PAGE 27 LINE 37