

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20,976-0000

LEASE NAME Wilson Opdyke

WELL NUMBER #1

DEC - 1 1999

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 32 TWP. 27 RGE. 5 (E) or (W)

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR Pintail Petroleum, Ltd.

COUNTY Sedgwick

ADDRESS 225 N. Market, Suite 300, Wichita, KS

Date Well Completed 10/10/80

PHONE# (316) 263-2243 OPERATORS LICENSE NO. 5086

Plugging Commenced 11/16/99

Character of Well SWD

Plugging Completed 11/18/99

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/16/99 (date)

By Steve Vangesen (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	259	
				4 1/2"	4287	1890'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Sanded to 4112', Bailed 4 sks port land shot 1890'
Pulled to 850' Pumped 35 sks. pulled to 350'. circulated cement to surface with 160 sks. Didn't get good cement. Let set up
Nest day 180' down to cement. Ran 1" tubing. circulated cement to surface with 55 sks. Hole stayed Full/

Name of Plugging Contractor Quality Well Service License No. 31925

Address 249 E. Beth Dr. Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pintail Petroleum, Ltd.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Walter Innes Phillips, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained, and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Walter Innes Phillips, Jr.

(Address) 225 N. Market, #300 Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1999

Patricia C. Byerlee
Notary Public



Expires: 12/11/2001

