


15-095-00188-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Kingman County. Sec. 33 Twp. 27S Rge. 5W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE
Lease Owner Laura Jane Oil Company, Inc.
Lease Name Johnson Well No. 1
Office Address 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 7-31-51 19
Application for plugging filed 7-31-51 19
Application for plugging approved 7-31-51 19
Plugging commenced 8-4-51 19
Plugging completed 8-4-51 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durke
Producing formation none Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	156	8 5/8	156'	none
Mississippi Dolomite		3781	3793	5 1/2"	3793	3142

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back with sand to 3770 and dump six sack cement at 3770. Top of mud in hole, 310', fill up with heavy mud to 10' below surface pipe. Set bridge plug top at 160'. 4' below surface pipe. Dump 15 sack cement. Fill with mud and cap top with 5 sack cement. Weld cap on top 8" pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Laura Jane Oil Company, Inc.
Address 817 Central Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS.
James Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
817 Central Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 9th day of August, 1951.

My commission expires 6/28/52

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

23-5091-s 8-50-10M
AUG 14 1951 8-14-51
CONSERVATION DIVISION
Wichita, Kansas

FILE SEC 23 27 5W
BOOK PAGE 127 LINE 78

15-095-00188-0000

DRILLING LOG

WELL NAME: Johnson #1
OWNERS: Laura Jane Oil Co., Inc.
CONTRACTORS: Laura Jane Oil Co., Inc.
COMM: 5-28-51
COMP: 6-11-51

LOCATION: SE SE SE, Sec. ³³23, 27S-5W
Kingman County, Kansas
ELEVATION: 1439 DF
1436 GR
CASING RECORD: 156' @ 5/8"
~~2793~~ 5 1/2" O.D.
PRODUCTION: 3793

<u>FORMATION</u>	<u>TO</u>	<u>TOPS</u>
Shale and Shells	360'	
Anhydrite	390	
Shale	595	
Shale and Lime	1625	
Shale and Shells	1930	
Sand and Shale	2060	Kansas City 2967
Shale and Lime	2595	Miss. Chat 3752
Lime	2680	Mississippian Dol. 3781
Lime and Shale	2967	
Lansing K. C.	3050	
Lime	3526	
Lime and Shale	3753	
Miss. Chat	3781	
Dolomite	3793 TD (Drilled in by Rotary)	

I certify that the above is a true and correct copy of the log of the Johnson No. 1, SE SE SE, Section 33-27S-5W, Kingman County, Kansas, to the best of my knowledge.

LAURA JANE OIL CO., INC.

BY: James Armour
James Armour,
Assistant Sec. & Treas.

Sworn and subscribed to before me this 13th day of June, 1951.

Carol J. Iner
NOTARY PUBLIC

My Comm. Expires 6-28-59.

PLUGGING
23 27 SW
10 v
BOOK PAGE

RECEIVED
AUG 14 1951
DIVISION
Wichita, Kansas