


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biffing Building
Wichita, Kansas

Kingman County, Sec. 33 Twp. 27S Rge. 5 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SW
Lease Owner Smitherman & Cohen, Etal
Lease Name Young Well No. 1
Office Address P. O. Box 692, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6 - 18 19 51
Application for plugging filed 6 - 30 19 51
Application for plugging approved 6 - 30 19 51
Plugging commenced 7 - 2 19 51
Plugging completed 7 - 5 19 51
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. Durkee
Producing formation Depth to top Bottom Total Depth of Well 3848 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3839'	3182'
				8 5/8"	150	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with chat from 3848' to 3775'
Run 6-sks. cement from 3775' to 3735'
Fill with mud from 3735' to 165'
Make solid with rock from 165' to 155'
Run 15-sks. cement from 155' to 110'
Fill with mud from 110' to 15'
Cap with 5-sks. cement from 15' to surface.

7-12-51
RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Smitherman & Cohen Drilling Company
Address P. O. Box 692, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
J. C. Smitherman (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. C. Smitherman
P. O. Box 692, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of July, 1951.

Edith S. Liggell
Notary Public.

My commission expires March 3, 1955

PLUGGING
NW 1/4 SEC. 33, T27R5W
E1/2 NW 1/4 LINE 44

15 095-00189-0000

YOUNG WELL #1

Company - Smithman & Cohen, etal
Contractors - Smithman & Cohen Drilling Co.

Location: NW NW SW, Sec. 33-270-5W
Kingman County, Kansas

Commenced - 6-5-51
Completed - 7-5-51
Total Depth - 3848'
L. F. - B & A

Dist. - 1147' N.E. 125
Cavings:
8" - 150' c/100 sacks
5 1/2" - 3039' c/30 sacks

Figures Indicate Bottom of Formations

Shale	150
Shale & Shells	710
Shale, Shells & Salt	1000
Shale & lime	1115
lime & shale	1490
Shale	1790
shale, lime & sand	2030
Shale & Shells	2345
Shale & lime	2440
lime	2555
Shale & lime	2825
lime	3145
lime & shale	3165
Shale & lime	3545
lime & shale	3782
Mississippi Chert	3830
lime	3848 F.O.

We hereby certify the above and foregoing to be a true and correct copy of the log of Young Well #1 located in the NW NW SW, Section 33-270-5W, Kingman County, Kansas.

SMITHMAN & COHEN DRILLING COMPANY

L. C. Smithman
L. C. Smithman

Subscribed and sworn to before me this 11th day of July, 1951.

My Commission Expires March 3, 1951

Edith L. Higgitt
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 33 T 27 R 5W
BOOK PAGE 9 LINE 44