


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County. Sec. 34 Twp. 27S Rge. 5 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Natural Gas and Oil Company
Lease Name Kroeker Well No. 1
Office Address P. O. Box 105 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-30 19 60
Application for plugging filed 1-30 19 60
Application for plugging approved Verbal - 1-30 19 60
Plugging commenced 1-31 19 60
Plugging completed 1-31 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation Depth to top Bottom Total Depth of Well 3802 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 240 feet
1/4 sack hulls, plug, 18 sacks cement through drill pipe
mud to 35 feet
1/4 sacks hulls, plug, 10 sacks cement to surface.
Bridge rat hole and put in 2 sacks dry cement
Complete 1:00 P.M. January 31, 1960.

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1960

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
I, J. B. Steele, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P. O. Box 105 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 60

Richard R. Brack
Notary Public.

My commission expires July 27, 1963



15-095-00111-0000

D R I L L E R S L O G

#1 Kroeker

CASING RECORD:	COMPANY:	Natural Gas & Oil Co.	DESCRIPTION:	NW NW NW
254.71' of new 8-5/8" surface casing	CONTRACTOR:	Strata Drilling, Inc.	Section	34-27S-5W
TOTAL DEPTH:	COMPLETED:	January 31, 1960	Kingman County,	Kansas
3802'	COMMENCED:	January 21, 1960		

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	160	Ran 254.71' (8 Jts.) of new 8-5/8" surface casing; set and cemented @ 263' with 170 sacks of cement, 2% gel and 2% C. C. Circ. out cement. Recement with 180 sacks of cement, 2% gel and 2% C. C. Plug down @ 9:00 A. M. 1-22-60.
Shale	264	955	
Shale & Lime	955	2468	
Shale	2468	2685	
Lime & Shale	2685	3195	
Lime	3195	3270	
Lime & Shale	3270	3349	
Lime	3349	3655	
Lime & Shale	3655	3740	
Lime	3740	3802	
Total Depth 3802'			DST #1 3755'-3769' tool open 1 1/2 hours, gas to surface in 22 min. Recovered 100' gassy mud. ISIP 1380 lbs. FSIP 1090 lbs. IFP 35 lbs. FFP 55 lbs.

RECEIVED
STATE OF KANSAS COMMISSIONER

FEB 4 1960

CONSERVATION DIVISION
Wichita, Kansas

Plugged bottom plug @ 240'. Plugged with 1/4 sack hulls, 18 sacks of cement, top plug @ 40', plugged with 1/4 sacks hulls, 10 sacks of cement. Plugged rat hole with 1 sack of hulls and 2 sacks of cement. Plug down @ 1:00 P. M. 1-31-60.

STATE OF KANSAS)
) ss:
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 2nd day of January, 1960.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1961

FEB - 3 1960