

15-095-00489-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 35 Twp. 27 Rge. (E) 5 (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Pickrell Drilling Company
Lease Name Branine Well No. 1
Office Address 705 4th National Bank Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 4, 1963
Application for plugging filed January 4, 1963
Application for plugging approved January 4 1963
Plugging commenced January 4 1963
Plugging completed January 4 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Toman
Producing formation Depth to top Bottom Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 180'. Set plug. Cemented with

20 sacks cement. Heavy mud to 40'. Set plug.

Cemented with 10 sacks cement to bottom of

cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1963

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebits
705 4th National Bank, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of January 8, 1963

My commission expires June 21, 1966

Maxine Blackman

Notary Public.



ROTARY DRILLING LOG

15-095-00489-0000

COMPANY: PICKRELL DRILLING COMPANY
705 4th Ntl Bank Building
Wichita 2, Kansas
LOCATION: Branine No. 1, C SW SW 35-27-5, Kingman County, Kansas

Rotary Drilling Commenced 12-26-62

Rotary Drilling Completed 1-4--63

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (8 jts) 8 5/8" Surface Casing set at 207', cemented with 160 sacks cement. Circulated. Completed 8:15 P.M. No oil string run. D&A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil & Sand	<u>C. F. S.</u>
207	Red Rock	3325
825	Red Rock & Shale	3367
1100	Shale & Shells	3745
1300	Lime & Shale	3755
1670	Lime	3765
2590	Lime & Shale	3775
2745	Lime, Shale & Sand	3785
2940	Lime & Shale	3790
3400	Lime	3800
3765	Lime & Shale	3830
3830	Mississippian (TD)	

Slope Tests

2500
3000
3500

S. L. M.

3367
3604

PICKRELL DRILLING COMPANY
STATE CORPORATION NO. 123456

JAN 11 1963

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 8th day of January, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Maxine Blackman
Maxine Blackman Notary Public

My commission expires: June 21, 1966