


15-095-21017-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 36 Twp. 27S Rge. 5W E/W-
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C-SW SE NW
Lease Owner Vincent Oil Corporation
Lease Name Durfee Well No. 1
Office Address 200 W. Douglas-Suite 10, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole



Date Well completed November 14, 19 80
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced November 14, 19 80
Plugging completed November 14, 19 80
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,865'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,865 ft. (rotary total depth) to 210 ft. Set plug at 210 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 210 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water-Suite 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1980

My commission expires July 25, 1982
Elsie Willison - Notary Public
Wichita, Kansas

RECEIVED
JAN 6 1981
CONSERVATION DIVISION
Wichita, Kansas
01-06-81

KANSAS DRILLERS LOG

COMPANY Vincent Oil Corporation

SEC. 36 T. 27S R. 5W

FARM Durfee NO. 1

LOC. C-SW SE NW

COUNTY Kingman

ROTARY TOTAL DEPTH 3,865'

COMM. November 6, 1980 COMP. November 14, 1980

CONTRACTOR H-30, INC. (Rig #2)

ISSUED November 20, 1980

CASING

10 3/4"

8 5/8" Set at 218' cemented w/200 sxs cement

ELEVATION 1,444' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	222'
Sand and Shale	901'
Shale	1,805'
Lime and Shale	1,995'
Shale	2,240'
Lime and Shale	3,330'
Shale	3,428'
Shale and Lime	3,500'
Lime	3,865'
Rotary Total Depth	3,865'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th day of November, 1980.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE GEOLOGICAL COMMISSION
JAN 6 1981
CONSERVATION DIVISION
Wichita, Kansas