


15-095-00737-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County. Sec. 13 Twp. 27 Rge. 20X (E) W (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW NW  
 Lease Owner Morgenstern & Spector  
 Lease Name McMichaels "A" #10 Well No. \_\_\_\_\_  
 Office Address Russell, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) oil  
 Date well completed 7-26-51 19\_\_\_\_  
 Application for plugging filed Nov. 10, 1959 19\_\_\_\_  
 Application for plugging approved Nov. 12, 1959 19\_\_\_\_  
 Plugging commenced 12-3-59 19\_\_\_\_  
 Plugging completed 12-5-59 19\_\_\_\_  
 Reason for abandonment of well or producing formation failure to produce profitably  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
 Producing formation Viola Depth to top 4278 Bottom 4279 Total Depth of Well 4281 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	285'	none
				5-1/2"	4272'	3089'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4284' and found it open.  
 Filled w/sand to 4260' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
 Cleared hole and mudded the hole to 200', set rock bridge to 190' and dumped 20 sacks of cement. Mudd@d the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

JAN 19 1960

Name of Plugging Contractor Knight Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)  
 Address Chase, Kansas CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 59

Thomas V. Dyer

My commission expires 9-27-62 Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-095-00737-0000

Company- LION OIL  
Farm- McMichael No. 10

SEC. 13 T. 27 R. 10W  
NE SW NW

Total Depth. 4285  
Comm. 7-14-51 Comp. 7-26-51  
Shot or Treated. Acid 500  
Contractor. R. W. Rine Drlg Co.  
Issued. 9-29-51

County Kingman  
KANSAS



Elevation. 1752

Production. Pmp 114 bbls / 27% wtr

Figures Indicate Bottom of Formations.

sand, clay	300
red bed, shale, shells	554
shale, shells	1525
lime, shale	1985
shale	2510
lime, shale	2685
shale	2870
shale, lime	3585
lime	3920
lime, shale	4020
lime, chert	4067
shale	4075
lime, shale	4093
lime	4125
lime, shale	4285
Total depth	

Tops:	
Lansing	3497
Miss.	4022
Viola	4278

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 11 1959  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

DATE 1/14/60

INV. NO. 706-w