

15-095-015250000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Kingman

County. Sec. 13 Twp. 27S Rge. (E) 10 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Ctr. SW/4 NW/4 NW/4

Lease Owner Lion Oil Company

Lease Name McMichael

Well No. 12

Office Address Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-23 19 51

Application for plugging filed 10-2 19 51

Application for plugging approved 10-2 19 51


Plugging commenced 10-2 19 51

Plugging completed 10-4 19 51

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee

Producing formation Depth to top Bottom Total Depth of Well 4044 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"		2812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 4044' to 4000' and ran 6 sacks of cement. Mudded hole from 3045' to 300', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35', set rock bridge and ran 5 sacks of cement. Plugging completed.

OCT 11 1951 10-11-51

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Vernon Hayes  
Address Box 639  
Pratt, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss.

Vernon Hayes (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes

Box 639, Pratt, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1951

My commission expires August 29, 1955

Van Stuebel  
Notary Public.

PLUGGING  
FILE SEC 13 T 27 R 10 W  
BOOK PAGE 115 LINE 29

15-095-01525000

McMICHAEL WELL No. 12

C. SW NW NW  
SEC. 13-27S-10W  
KINGMAN COUNTY, KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: AUGUST 3, 1951

FINISHED: AUGUST 14, 1951

LOG

SURFACE SOIL AND SAND	0 - 40	
SAND AND CLAY	40 - 150	
RED BED AND SHALE	150 - 312	8-5/8" Csg. @ 310' w/250 SX.
RED BED AND SHALE	312 - 550	SYFO @ 500' - OK
SHALE AND SHELLS	550 - 1150	SYFO @ 1000' - OK
SHALE AND SHELLS	1150 - 1330	
LIME	1330 - 1850	SYFO @ 1500' - OK
LIME AND SHALE	1850 - 2145	
LIME	2145 - 2195	
SHALE	2195 - 2325	
SHALE	2325 - 2700	SYFO @ 2500' - 10
SHALE AND LIME	2700 - 2890	
SHALE AND LIME	2890 - 3155	SYFO @ 3000' - OK
SHALE	3155 - 3180	
LIME	3180 - 4015	
MISSISSIPPI CHERT	4015 - 4060	
LIME AND CHERT	4060 - 4105	
LIME	4105 - 4170	
SHALE	4170 - 4230	
SHALE	4230 - 4283	5 1/2" Csg. @ 4282' w/200 SX.

STATE OF KANSAS }  
                          } ss.  
COUNTY OF SEDGWICK }

I, E. H. SLOYER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE McMICHAEL WELL No. 12, LOCATED C. SW NW NW, SECTION 13-27S-10W, KINGMAN COUNTY, KANSAS.

E. H. Sloyer  
SECRETARY - TREASURER

SUBSCRIBED TO AND SWORN BEFORE ME THIS 24TH DAY OF AUGUST, 1951.

Louise Peterson  
NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1951  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 13-T-27R-10W  
BOOK PAGE 115 LINE 29